X-ray Tube Voltage (kilovolt peak)		Minimum HVL	
		(mm of aluminum)	
Designed operating	Measured operating	X-ray systems manufactured before	X-ray systems manufactured on or after June 10, 2006
range	potential	June 10, 2006	
Below 51	30	0.3	0.3
	40	0.4	0.4
	50	0.5	0.5
51 to 70	51	1.2	1.3
	60	1.3	1.5
	70	1.5	1.8
Above 70	71	2.1	2.5
	80	2.3	2.9
	90	2.5	3.2
	100	2.7	3.6
	110	3.0	3.9
	120	3.2	4.3
	130	3.5	4.7
	140	3.8	5.0
	150	4.1	5.4

TABLE I - HALF-VALUE LAYER FOR SELECTED kVp